

# KLC Trailer 3 akslet wirehejs til 6,0 - 6,5 mtr containere, Container system



Scanvo Trucks Danmark A/S  
 Hårup Skovvej 7, Hårup  
 8600 Silkeborg

Sælger  
 Salgsafdeling  
 salg@scanvo.dk  
 +45 8724 4370  
 +45 3046 2148 / 2498 2148 / 2497 2148

Registration		Weight		Hoist	
Model year	2013	Loading capacity kg	19400	Wire	✓
Reg. date	29-07-2013	Overall weight kg	25000	Make	KLC
Latest inspection	30-05-2024	Tare weight kg	5600	Type	CL 428
Chassis number (VIN)	UH9KHT20607KM1229	King pin kg	1000	Serial number	3065
Ref. no.	7358	<b>Coupling</b>		3 way tilt	✓
<b>Basis</b>		Electrical coupling	13 polet EBS + 7 polet lysstik		
Type	Drawbar	Air-coupling	Duo-matic		
Aksel	3	Manufacturer	57 mm trækøje		
Stand	Fine	V "KN air"	54		
<b>Tyres</b>		V "KN no air"	72		
% remaining	60/80 - 80/70 - 70/50	Coupling height mm	750		
Dimensions	275/70R22,5	Coupling pressure	1000		
<b>Brakes</b>		<b>Dimensions</b>		<b>Tippers</b>	
Drum brakes	✓	Height mm	Til hejs 1200		
ABS	✓	<b>Suspension</b>		3-way ✓	
<b>Chassis</b>		Air	✓		
Toolbox	✓				
Total length mm	8000 - 8300				
Hydraulic 2.	✓				
Working light	✓				
Shaft type	SAF				
Axle load kg	8000				

## Beskrivelse

KLC 3-axle cable hoist trolley

KLC cable hoist with 3-way tip, year 6/2008 no 3065 - remote control for the hoist  
 6000 - 6500 mm container boxes - 1200 mm height on rollers for hoist  
 2 container stops: 1st stop dimension 4900mm, 2nd stop dimension 5400 mm - 2600 mm from wire roll to draw eye  
 manual extendable bumper, can be moved out 300 mm  
 SAF axles with drum brakes - Air suspended  
 Toolbox  
 Additional work light.  
 Towing eye, 57 mm - coupling height currently 750 mm can be changed in height from/to 600 - 850 mm.  
 Coupling length 8000-8300 mm

Delivered with a new look from 30/5-2024 - new brake shoes on all wheels and new steel wire on the hoist

~~Contract Scanvo Trucks +45 87 24 43 70 or via email: salg@scanvo.dk~~



